Substructure

Piled foundations, pile caps, piling mat 9,250m² @ £95

Suspended reinforced concrete slab, typically 275mm thick, ground beams, insulation and DPM 9,250m² @ £125

Allowance for gas membrane to building footprint 9,250m² @ £36 Allowance for below-ground ducts, pits and sumps 9,250m² @ £12

8.82% Frame and upper floors 4,189,800 186.21

Structural steelwork, columns and beams generally including erection and surface

treatments 450t @ £1,450

Structural steelwork, UC section columns, fabricated plate sections to take arena

cantilevers, average rate including erection and surface finishes 300t @ £1,600

Structural steelwork, fabricated plate girder and UB arena raker/cantilever beams,

including erection and surface finishes 300t @ £2,100 Intumescent paint 750t @ £400

200mm thick precast concrete slabs with structural concrete topping 5,250 @

Composite metal deck with insitu reinforced concrete filling 2,300m² @ £100 Precast concrete L-shaped units to arena rake, 875mm x 474mm high on locating

pins, sealed joints 5,705m² @ £200

Allowance for secondary steelwork, trimming to openings, etc., item @ £100,000

4,197,400 186.55 8.84%

Steel roof structure; fabricated trusses spanning 60m, walkways and rigging grid. Average weight 75kg/m². Rate includes temporary works for final on-site assembly, erection and paint system 700t @ £2,500

Composite standing seam roof system on structural decking and secondary steelwork,including lining and thermal insulation, rate enhanced for additional dead

loads for acoustic insulation $9,250 \, \text{m}^2$ @ £120 Extra for horizontal and vertical acoustic lining to arena roof 8,850m² @ £70

Allowance for service yard roof including acoustic treatment 2,000m² @ £130 Allowance for feature canopies to box office and entrances, structural glazing, item

@£50,000 Extra for rooflights and roof vents, item @ £75,000

Allowance for roof detailing, abutments, eaves and upstands 360m @ £260

Mansafe system, item @ £35,000

1,000m² @ £250

Floor finishes

Rainwater installations to main roof and canopies, complete 11,350m² @ £18

SHELL COSTS $\text{£/m}^2\,\text{GIFA}$

Internal walls and partitions 1,900,000 84.44 4.00% 200mm thick concrete walls forming vomitories and upstands within seating bowl

 $140\ \text{mm}$ blockwork in dividing walls and partitions, up to 6m high including lateral and vertical restraint 19,000m² @ £60

Drywall partition, generally 1 hour FR $900m^2 @ £60$

Aluminium framed glazed screens 800m² @ £360

WC cubicles - vandal resistant 300nr @ £560

Decorative coverings on plaster 1,000m² @ £40

Internal doors 1,426,300

High quality solid core veneer doors and frames, stainless steel ironmongery, to premium areas, rate for single leaf 80nr @ £1,500 Solid core laminate faced or steel doors and frames, stainless steel ironmongery, in

front and back of house areas, average rate for single leaf 460nr @ £1,200Duct and service riser doors 32nr @ £1,000

Sliding timber faced folding partitions, 3.0m high $386m^2 \ @ £800$ Glazed openable screens to suites and boxes 400m² @ £580

Fire and security shutters to concessions, bars and area segregation $550 m^2 \ @ £330$

Wall finishes 0.73% 346,300 15.39 Ceramic tiling on render 550m² @ £75 Emulsion paint on plaster 3,000m² @ £15

Paint concrete or masonry 14,000m² @ £5 Allowance for panelling and other decorative finishes Item @ £150,000

Carpet, various grades, including levelling screed and skirtings, average rate used 2,020m² @ £40

Vinyl sheet, various grades, including levelling screed and skirtings $1,500 \text{m}^2 \otimes £35$ Stone / terrazzo flooring including screed and skirtings $480 \mbox{m}^2$ @ £200

614,300

Ceramic tiling including screed and skirtings 500m² @ £100 Epoxy floor coatings and sealers, various grades, to Arena floor, plant areas etc,

average rate used 15,000m² @ £18 Entrance matwells and mats 130m² @ £500

22.00 495,000 1.04% Ceiling finishes

Egg crate and tile suspended ceilings, average rate used 1.100m² @ £50

Plasterboard suspended ceiling on MF with skim finish and edge trim 2,500m² @

Sealer to structural soffits 12,250m² @ £10 Allowance for special finishes, bulkheads, smoke curtains and suspended features

Item @ £230,000

155.04 Furniture and fittings 3,488,500 7.34% Fixed padded seating to general admission areas 7,500nr @ £75

Fixed padded seating with arms to club areas 800nr @ ±95 Fixed upholstered seating with arms to suites 200nr @ £180 Retractable/moveable seating systems to front of lower bowl 1,500nr @ £350

Safety rails and barriers to fixed seating bowl 2,000m @ £350 $\,$ Vanitory units, item @ £150,000

Integrated plumbing systems, back panels and duct casings 600nr @ £500

Signage; safety, directional and statutory, item @ £90,000 Fixtures and fittings to toilets, changing rooms, dressing rooms and offices, item @

Fit out and fixed furnishings to suites, lounges, bars and club areas, item @ £220,000 Glass division screens, upstands and shelves to suites 20nr @ £3,200

Drinks rails, shelves and queuing rails to concourse areas, item @ £50,000 General fixtures and fittings, item @ £75,000

Catering fit out including fixed equipment only to kitchens, concessions and restaurants, item @ £440,000

BMS controls 22,500m² @ £15 390,000 0.82% Builder's work in connection 17.33 Forming holes, chases, etc.; allow 3% @ £390,000

337,500

8,339,100

15.00

370.63

0.71%

17.56%

Contractor's overheads, site establishment and site supervision; allow 15% @ £5,886,900

Testing and commissioning of building services installations, item @ £200,000 Design reserve; allow 5% @ £2,252,200

Total construction cost - shell costs only 47,500,000 2111.09 100.00%

OPERATOR'S FIT-OUT AND DIRECT CONTRACTS

Furniture and fittings

Office furniture, fittings and equipment, item @ £75,000

Dressing room fittings and equipment, item @ £15,000

Medical room, post room and box office fittings, item @ £10,000 $\,$ Allowance for miscellaneous fittings and equipment, item @ £100,000

Electronic systems

Ticketing systems and barriers, item @ £50,000 Electronic information boards, item @ £50,000Telephone system, item @ £50,000

EPOS systems, item @ £100,000

Special installations

Preliminaries and contingencies

IT installation and servers (main infrastructure in shell works), item @ £100,000

FM and building management Waste management and compactor, item @ £15,000

Forklift and access equipment, item @ £40,000

Workshop equipment, item @ £15,000 Ride on cleaner, sweepers, scrubbers and cleaning equipment, item @ £50,000

Excavation for footings, bases and filling to levels; limited off site disposal 9,250m²

6.04%

127.44

2.867.500

Reinforced concrete stairs and landings with float finish and non-slip inserts 420m² @£600

Feature stairs to VIP and club areas; architectural steelwork 75m² @ £1,000

Precast step units to form gangway steps on seating aisles 1,000nr @ £60

Precast step units to vomitories, cross aisles, etc. 100m² @ £550

Stairs and ladders to roof and roof walkway access, plant room stairs and catwalks, item @ £25.000 Balustrades and central division rails designed to assembly load criteria, average

rate for finishes including galvanised or stainless steel, polyester powder coating, etc., 560m @ £460

Staircase handrails; average rate 560m @ £130

Internal and external safety handrails, gantries, walkway guardrails; galvanised steel 1,250m @ £200

Insulated masonry wall to service level, architectural blockwork, including allowance for windposts, etc. 2,000m2 @ £200 Composite insulated metal cladding panels on cladding rails (blockwork substrate

5,066,600

225.18 10.67%

External walls, windows and doors

Disposal installations

Water installations

Electrical installations

Lift installations

£750.000

HV installations 22,500m² @ £14

External facade lighting, item @ £75,000

3.00%

1.29%

63.39

27.30

measured separately) 7,000m² @ £230 Curtain walling with 40% glazing and metal transom panels; stick system 3,000m² @£450

Allowance for feature elevation in Structural glass walling 500m² @ £600

Aluminium louvres 520m² @ £380 Allowance for solar shading and other elevation features, item @ £100,000

Allowance for blockwork backing and lining walls to cladding, windposts 9,000m² @ Cladding to soffits and eaves 1,100m² @ £180

Main entrance doors in laminated glazing 28nr @ £10,000 Extra over metal cladding for double doorsets 10nr @ £5,000

General fire escape and plant room doors and frames, ironmongery, average rate per leaf 76nr @ £1,500

Power operated insulated shutters to service yard 200 m 2 @ £310

£/m² GIFA 431,000 Sanitary installation 19.16 0.91% Fittings generally 940nr @ £400 Showers 50nr @ £1,100

683.800

702,000

3,507,500

30.000

600,000

30.39

31.20

155.89

1.33

26.67

98.44

84.44

n/a

n/a

1.44%

1.48%

7.38%

0.06%

1.26%

4.66%

Below ground drainage pipework, chambers, pumps and attenuation $9,250 \, \text{m}^2$ @ £35 Above ground waste, soil and vent pipework 22,500m² @ £16

Mains water supplies, storage and distribution 22,500 m 2 @ £5 Central boilers, flue, pumps, pressurisation and calorifiers 22,500m² @ £9

Hot and cold water distribution, complete 22,500m² @ £16 Local hot water heaters to toilets and concessions, item @ £27,000

180.89 8.57% Space heating and air treatment 4,070,000 LPHW distribution and emitters, generally 22,500m 2 @ £18 Air handling, supply and extract to arena bowl and concourses 14,500m² @ £130

Air handling, extract and heating to general areas $8,000 m^2 \ @ £120$ Chilled water plant room and distribution, serving suites and club lounges only 4,000m² @ £20

Chiller installation, item @ £75,000 Local cooling units, item @ £50,000 Door curtains to entrances, item @ £75,000

Extract ventilation to toilets, kitchens and concessions 2,500m² @ £100 Smoke extract installations $14,500 \text{m}^2$ @ £20

LV distribution including show supplies 22,500m² @ £35 General LV power 17,500m² @ £10 Power to lifts, mechanical plant, seating and operator's equipment, item @

Standby generators and UPS systems, item @ £150,000

Allowance for containment 17,500m² @ £14 Lighting installations generally including feature lighting 17,500m² $\ @\ £45$

Emergency lighting 22,500m² @ £15 Arena bowl lighting 6,000m² @ £35 Stage and gantry bus bars, panels and lighting installations, item @ £200,000 $\,$

Specialist lighting controls, item @ £100,000

Gas installations Incoming gas supply and distribution, item @ £30,000

Electro-hydraulic 2,500kg passenger/goods lift serving 4 levels 4nr @ £110,000 Electro-hydraulic 1,000kg passenger/goods lift serving 4 levels 2nr @ £80,000

555,000 1.17% 24.67 Protective installations

Earthing and bonding and lightning protection 22,500m² @ £4 Sprinkler installations 17,500m² @ £22

Communications installations Fire alarm and smoke detection interfaced to PA system 22,500m 2 @ £15

Card access and intruder alarm system, item @ £125,000

Hose reel and dry riser installations, item @ $\pm 80,000$

TV ariel, cable installation, including digital distribution equipment, item @£125,000

Public address and digital music broadcast system $22,500 \, \text{m}^2$ @ £22

CCTV system including IP interface 22,500m² @ £10 Fibre backbone and ICT infrastructure including an allowance for data points, item @

Allowance for containment for communications systems and for future operator systems 22,500m2 @ £7

Show systems and equiment Demountable stage with mixing platform, item @ £200,000

Rigging latchlines, item @ £70,000 Event cabling, item @ £20,000 Event lighting, item @ £20,000

Loose catering and kitchen equipment, item @ £60,000 Concession fitting out and equipment, item @ £100,000

Concession and hospitality fit-out

Radio equipment, item @ £20,000

Loose seating, item @ £90,000

Safes, item @ £25,000

Merchandise stand fitting out and equipment, item @ £30,000 Club lounge fixtures and equipment, item @ £60,000

Auditorium drapes and tracks, item @ £60,000

Restaurant fixtures and equipment, item @ £50,000 Suite furnishings and equipment, item @ £400,000 Concourse lounge fixtures and equipment, item @ £25,000

Operator's scope and interface contingency @ 15%

Total operator's fitout and direct contracts 1,900,000

Total cost (excluding external works) 49,400,000 2,195.53

ACKNOWLEDGEMENTS

We would like to thank Mike Cowley of SMG and John Rhodes of Populous, together with Richard Grover, David Porter and Alan Willby of the Davis Langdon Specialist Sports Team for their input into this cost model.